



GOVERNMENT OF ODISHA  
OFFICE OF THE PROJECT DIRECTOR-CUM-CHIEF ENGINEER  
PROJECT MANAGEMENT UNIT, MEGA LIFT PROJECTS  
PLOT No. - A - 8/2, BHOI NAGAR, BHUBANESWAR - 751022  
E-mail Id: - cemegalift-eicwr.od@nic.in, Telephone No. 0674-2567252

No. 2913 /Dated. 24.9.2015

**QUOTATION CALL NOTICE NO. 03/2015-16**

The Project Director-cum-Chief Engineer, PMU, Mega Lift Projects, Bhubaneswar invites sealed quotation in Plain Paper from the reputed Contractors/ Firms dealing with feasibility study of irrigation projects as per the detailed Terms of Reference given below for "Exploring possibility/feasibility study of new Mega Lift Schemes in the 21 Blocks at different Districts in the State of Odisha as in Annexure-A" which will be received up to 3.00 PM of 15.10.2015 and will be opened on the same day at 3.30 PM.

The rate should be quoted both in figures and in words per Ha. of CCA. Taxes payable, if any, as per the prevailing Government rules should be mentioned in the quotation.

The quotationers are requested to attach true copy of valid and up to-date VAT Certificate and PAN along with their quotation failing which the quotation will be rejected.

The quotation must be accompanied with E.M.D of Rs. 10000/- (Rupees Ten Thousand only) in shape of NSC/KVP/Post office time Deposit/Deposit Receipts of scheduled bank duly pledged in favour of Executive Engineer, Mega Lift Projects, Bhubaneswar.

The intending quotationers should submit their quotations through Registered post/Speed post only. The undersigned will not be held responsible for postal delay, if any. The quotations received after the scheduled date and time shall not be entertained.

The work should be completed within 20 days from the date of receipt of the order. The authority reserves the right to reject any or all the quotations without assigning any reasons thereof.

**TERMS OF REFERENCE FOR PRELIMINARY SURVLEY OF MEGA LIFT SCHEMES**

1. Conduct the feasibility study for providing irrigation through Mega Lift Schemes in the Blocks mentioned in Annexure-A for the un-commanded CCA
2. Find out the source from which the required water is to be lifted.
3. Collection of data of Highest observed flood level in case of river lift at the Intake and Pump House Site.
4. Fix up the Locations of Pump House indicating Latitude and Longitude, Distance from Intake, Reduced Level at the location.
5. Fix up the boundaries of the Command Area proposed and demarcate on maps.
6. Tentative locations of Delivery Chamber from the consideration of piped irrigation supply to command area, with the data of latitude and Longitude and Reduced Level
7. Provide details of existing 33/ 11 KV substations of the concerned Distribution Company. It is desired that the relevant topo sheets to the Scale of 1:1,00,000 shall be provided.

Similarly the Latitude and Longitude of existing 132/ 33KV or 220/ 33 KV E.H.T. substations of OPTCL may be indicated.

All the detailed report on feasibility study to be submitted both in soft and hard copy marked on topo sheets.

Encl: As above.

*[Signature]*  
Project Director-cum-Chief Engineer  
PMU, Mega Lift Projects, Bhubaneswar

Memo. No. 2914

Dated. 24.9.2015

Copy forwarded to the Director, Information & Public Relation Department, Government of Odisha, Bhubaneswar for information and necessary action. It is requested to publish the quotation call notice in two Odia Daily Newspaper on or before 08.10.2015 consuming minimum space. Complimentary copy of the Newspaper may be sent to this office for record.

*[Signature]*  
Project Director-cum-Chief Engineer

Memo. No. 2915 (2)

Dated. 24.9.2015

Copy to the Engineer-in-Chief, Water Resources/ Engineer-in-Chief, P&D, Odisha, Bhubaneswar for favour of kind information.

*[Signature]*  
Project Director-cum-Chief Engineer

Memo. No. 2916 (4)

Dated. 24.9.2015

Copy to the Executive Engineer, Mega Lift Projects, Bhubaneswar/ Titilagarh/ Sonapur/ Jepore for information and wide circulation.

*[Signature]*  
Project Director-cum-Chief Engineer

Memo. No. 2917 (2)

Dated. 24.9.2015

Copy to the Project Manager, OCTMP, Bhubaneswar/ Superintending Engineer, Central Minor Irrigation Circle, Bhubaneswar for wide circulation with a request to display the notice in the Notice Board.

*[Signature]*  
Project Director-cum-Chief Engineer

Memo. No. 2918 (2)

Dated. 24.9.2015

Copy to Notice Board/ Work File for information and wide Circulation.

*[Signature]*  
Project Director-cum-Chief Engineer

## List of Block with un-commanded CCA

Sl. No.	Name of District	Name of Block	Un-command cultivable area (Ha)	Area required to achieve 35 % irrigational potential in (Ha.)	Rate per Ha. (In word and figure)
1	2	3	4	5	6
1	Bolangir	Belpada	23938	662	
2	Bolangir	Patnagarh	28448	1720	
3	Jagatsinghpur	Erasama	15882	2528	
4	Kandhamal	Daringibadi	8346	1232	
5	Kandhamal	Kotagada	7350	421	
6	Kendrapara	Rajnarar	20413	4488	
7	Keonjhar	Bansapal	10418	135	
8	Keonjhar	Joda	11934	1521	
9	Keonjhar	Saharpada	17519	951	
10	Koraput	Baipariguda	19413	2115	
11	Koraput	Nandapur	15731	1573	
12	Malkangiri	Khairput	7193	677	
13	Malkangiri	Mathili	33247	3528	
14	Mayurbhanj	Bisoi	13962	1439	
15	Mayurbhanj	Karanjia	13969	781	
16	Mayurbhanj	Tiring	8069	238	
17	Nabarangpur	Kosagumuda	22585	840	
18	Nabarangpur	Papadahandi	15296	508	
19	Puri	Krushnaprasad	13261	4271	
20	Rayagada	Kasipur	25300	1169	
21	Sundargarh	Nuagaon	21540	3678	
<b>Total</b>			<b>353814</b>	<b>34475</b>	